BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

SCHDULE-B

Name of Work: Improvements to Rangamandhira at Bagalagunte (Near Maramma Temple) in ward No:14 Bagalagunte

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures	In Words (Rs)
1	2	3	4	5	6
1	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40 mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth,including cost of all materials, labour HOM of machinery curing complete as per specifications.	CUMT	30.00	4757.28	Rupees Four thousand seven hundred fifty Seven & Twenty Eight Paise Only
2	Flooring with 20 mm think polished shahabad slabs using cement morter 1:6 , 25 mm thick over existing cement concrete bed or top roof laid to line and level and joints with cement slurry mixed with pigment to muatch the shade of the slab including cost of materials, labour curing polishing complete as per specification	SQMT	196.00	1175.54	Rupees One thousand One hundred Seventy Five & Fifty Four Paise only
3	Providing and fixing Stainless steel staircase raling as per Chief Architect Drawing No.11520/H`C with hand rail 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage stainless steel vertical pipe spaced at 1.20m regular intervals and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour HOM of machineries and electrical charges etc complete as per specifications.	SQMT	9.60	6393.92	Rupees Six thousand three hundred Ninty Three and Ninty Two Paise only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer

Scanned by CamScanner

4	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after throughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.	Sqm	117.80	67.84	Rupees Sixty Seven & Eighty Four Paise Only
5	Providing and applying painting two coats (excluding priming coat) on new wood surface and/or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications	SQMT	5.04	82.68	Rueeps Eighty Two & Sixty eight paise only
6	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.	SQMT	28.80	80.56	Rueeps Eighty & Sixty Fifty Six paise only
7	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	SQMT	91.00	57.24	Rupees Fifty Seven & Twenty Four Paise Only
8	Providing and fixing M.S grill work for windows and ventilators weighing 21kg/sqm using M.S flats, or M.S. square rods, or combination of M.S flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications	Rmtr	2.10	98.58	Rupees ninty Eight & Fifty Eight Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer

Scanned by CamScanner